

- 1. PRIMING OF THE SUBSTRATE MAY BE REQUIRED, FOLLOW SPECIFICATIONS AND MANUFACTURER RECOMMENDATIONS.
- 2. REINFORCEMENT MUST BE FULLY SATURATED OR ENCAPSULATED IN BASE COAT AS DESCRIBED IN SPECIFICATIONS.
- 3. THE EXISTING LOOSE GRAVEL MUST BE REMOVED AND THE ROOF MUST BE REPAIRED PER MANUFACTURER REQUIREMENTS PRIOR TO APPLICATION OF THE LEVELING COAT.



SHEET TITLE:

STRUCTURAL ROOF MEMBER
THROUGH ROOF DECK
GRAVEL BUR RESTORATION

SCALE:

NTS

DRAWING No.:

DWG NO. LA-GR-14